

CONSENSUS Street	termini	termini	length	width	recommended treatment	SY	Cost
Kilm Waveland Cutoff	Hwy 90	Hwy 603	7500	22	patch level surface 2", stripe	18333.33	\$ 469,775.05
Central	Coleman	Nicholson	4100	21	patch level surface 2", stripe	9566.667	\$ 122,307.17
Old Spanish Trail	Hwy 90	Nicholson	5780	22	Patch, Level, resurface 2"	14128.89	\$ 241,416.62
Waveland Ave	Beach Blvd	Central	4370	22	diamond grinding	10682.22	\$ 250,000.00
CONSENSUS TOTAL							\$ 1,083,498.84
Engineering							\$ 130,019.86
Total project							\$ 1,213,518.70
CONSENSUS TOTAL							\$ 1,213,518.70
WARD 1 TOTAL							\$ 339,670.25
WARD 2 TOTAL							\$ 210,103.38
WARD 3 TOTAL							\$ 233,685.69
WARD 4 TOTAL							\$ 759,299.93
CITYWIDE TOTAL PROJECT COST							\$ 2,766,277.95
INCLUDING ENGINEERING							

Street	termini	termini	length	width	recommended treatment	SY	Cost
WARD 1							
Nicholson	Beach Blvd	top of slope	110	45	remove and replace; or diamond grind	550	\$ 5,239.01
Keller	Turner	2nd house around corner	780	10	reclaim/pave 2"	866.6667	\$ 17,286.97
Sixth	Nicholson	Turner	600	17	levelling and resurface 1.5"	1133.333	\$ 10,885.50
Fayard	curve	east end	1680	12	levelling and resurface 1.5"	2240	\$ 23,470.76
Turner	manhole	south of Sixth	15	15	manhole south of 6th was good; manhole in intersection of 6th and Turner - patch 15'x15' and raise manhole	25	\$ 1,460.00
Jeff Davis	Manhole	east of Nicholson			Did not find		
Jeff Davis	St Joseph	Nicholson	3900	17	Road is in good shape; if anything - ultrathin	7366.667	\$ 32,161.69
Lizana			850	10	Levelling and resurface 2"	944.4444	\$ 12,095.00
Edwards			380	10	Levelling and resurface 2"	422.2222	\$ 5,407.17
Longo	230' west of Breland	300' east of Turner	1600	16	Patch, level and pave 1.5"	2844.444	\$ 28,313.93
McKinley	Breland	Turner	610	11	Patch, level and pave 1.5"	745.5556	\$ 8,185.47
Daniel	Breland	Turner	640	12	Levelling and resurface 1.5"	853.3333	\$ 8,196.14
Turner	McKinley	Daniel	320	12	Levelling and resurface 1.5"	426.6667	\$ 4,098.07
Henderson	Nicholson	OSP	1500	20	Levelling and resurface 1.5"	3333.333	\$ 32,016.17
Henderson	OSP	Bismark	1800	13	Patch, level and pave 2"	2600	\$ 36,525.59
Hope	Arnold	east end	670	10	resurface 2"	744.4444	\$ 8,667.00
Ladner	Nicholson	Hwy 90	1550	17	Patch, level and pave 1.5"	2927.778	\$ 33,998.68
Victoria	Ladner	Arnold	650	13	resurface 2"	938.8889	\$ 10,930.77
St. Joseph	Manholes	N & S of Amelda	30	30	2 manholes S of Amelda - 15 x 15 patch and raise manholes	100	\$ 4,487.56
Farve	southern end	Hwy 603	930	11	reclaim & pave 2"	1136.667	\$ 20,451.54
Faith	Henderson	BSL City Limit	330	12	reclaim 135LF, resurface 2" entire length	440	\$ 5,920.00
Blenville	Beach Blvd	Bay Oaks Dr	1730	24	Linear mill 4" wide for curb tie-in, resurface 1.5"	4613.333	
							\$ 303,277.01 WARD 1 TOTAL
							Engineering \$ 36,993.24
							Total project \$ 339,670.25

Ward 2	Street	termini	termini	length	width	recommended treatment	SY	\$
	Morris	Olivari	intersection	300	15	20' patch and resurface 75' in all directions 2"	500	\$ 6,752.50
	Morris	Hart	intersection	300	15	20' patch and resurface 75' in all directions 2"	500	\$ 6,752.50
	Tabor	Morris	Edna	1330	16	levelling and resurface 2"	2364.444	\$ 30,280.18
	Tabor	Barlow	intersection	300	13	resurface 75' in all directions 2"	433.3333	\$ 5,044.97
	Tabor	Hogan	intersection	300	13	resurface 75' in all directions 2"	433.3333	\$ 5,044.97
	Dicks	Tabor	intersection	150	13	resurface 75' both sides of Tabor 2"	216.6667	\$ 2,522.49
	Dicks	Dixie	intersection	350	13	resurface intersection and all of Dicks 2"	505.5556	\$ 5,885.80
	Chagnard	Combel	St Joseph	1340	12	resurface 1.5" with 150' repair over culvert option - only repair 150' over culvert - \$1500	1786.667	\$ 16,764.83
	Combel	Music	intersection	150	15	resurface 75' both sides of Combel 2"	250	\$ 2,910.56
	Venus	Music	Tarpon	1570	12	resurface 2"	2093.333	\$ 24,371.09
	Honeys	S end	OST	1000	10	Patch and resurface 2"	1111.111	\$ 14,177.66
	Central	Vacation	St Joseph	2125	20	diamond grinding	4722.222	\$ 44,981.39
	Louisa	Mitchell	Nicholson	370	11	reclamation & pave 2"	452.2222	\$ 8,136.63
	Mitchell	Louisa	Nicholson	360	11	reclamation & pave 2"	440	\$ 7,916.72
	Gwen Ave	Louisa	Nicholson	350	10	shaping, compacting, level 1" and surface 1.5"	400	\$ 6,050.00
								\$ 187,992.30 WARD 2 TOTAL
								Engineering \$ 22,511.08
								Total project \$ 210,103.38

Street	termini	termini	length	width	recommended treatment	SY	
Ward 3							
Oak	2 pot holes		1300	18	Consider paving/levelling entire road; 200' at south end is worst, a couple of settled spots, one around manhole	2600	\$ 44,473.36
Vacation	top of culvert		150	18	Level & pave over culvert	300	\$ 5,239.01
Marcus	southern culvert	Central	950	15	Patch, Level, Pave 2"	1583.333	\$ 23,963.61
Sandy	bad spot		20	20	patch around manhole	44.44444	\$ 2,088.55
Sycamore	Villere	Amar	670	15	patch and overlay	1116.667	\$ 13,951.88
Villere	Sycamore	east end	280	12	road is in good shape - ultrathin	373.3333	\$ 1,629.91
Carroll	Waveland	250' east of Monroe	1200	15	patch, level, pave 1.5"	2000	\$ 22,003.84
Monroe	Carroll	north 150'	150	15	looked in good shape? Ultrathin	250	\$ 1,091.46
Margie	Ryan	Intersection	300	14	Margie 18' wide; ryan 10'; used avg of 14'; patch ryan either side	466.6667	\$ 8,731.68
Ryan	Sharon	Intersection	200	12	Margie; pave margie 7.5' either side of Ryan 1.5"	266.6667	\$ 7,761.49
Margie	Zimmerman	Intersection	50	12	100' patch down Sharon, pave Ryan 100'	66.66667	\$ 1,862.76
Boyd	west end	Margie	800	12	50' patch on Zimmerman	1066.667	\$ 11,176.55
Central	Waveland	Vacation	3000	20	patch and resurface 1.5"	6666.667	\$ 63,503.14
Rue De Lasalle	Sycamore	Intersection			diamond grind		\$ 1,190.68
Birch	Waveland Ave	Sycamore	420	15.5	replace culvert/resign ditch	723.3333	\$ 5,957.50
Birch	Sycamore	east end	430	10.5	resurface 1.5"	501.6667	\$ 2,069.38
					10.5 was done not too long ago? Some cracking, ultrathin		\$ 208,647.94 WARD 3 TOTAL
						Engineering	\$ 25,037.75
						Total proje	\$ 233,685.69

Ward 4	Street	termini	termini	length	width	recommended treatment	SV
	S Central	west end	Waveland	1100	20	Level and pave 2"	\$ 31,304.70
	Kingston	west end	Waveland	260	10	ultra thin	\$ 1,261.24
	Danube/Volga	Poe (N end)	KWC	1,370	12	patch level and resurface 2"	\$ 25,628.46
	Poe	Volga	Danube	480	12	excavate 6" and replace with 610 base, pave 2"	\$ 29,279.56
	Iris	Dogwood	Hibiscus	240	15	50' patch but otherwise good road, microsurface	\$ 4,074.78
	Superior	Niagra	Hudson	960	12	reclamation & pave 2"	\$ 23,030.47
	Niagra	Ave D	Huron	1,000	15	patching and resurface 2"	\$ 30,657.90
	Niagra	Coral	Lake	500	15	patching and resurface 2"	\$ 17,657.40
	Coral	Ave D	500' east	500	14	seal, level resurface	\$ 12,430.15
	Coral	500' west	Ave B	500	14	seal patch level resurface 2"	\$ 18,949.81
	Gulf St	Ave D	1st Ave	3,100	12	excavate 6" and replace with 610 base, pave 2" alternate - reclamation and pave 2" - \$70,266	\$ 189,097.14
	Lake	Ave D	1st Ave	3,100	12	seal patch, level, pave 2"	\$ 66,527.77
	Ocean	Ave D	Ave B	1,600	12	excavate 6" and replace with 610 base, pave 2" alternate - reclamation and pave 2" - \$36,266	\$ 97,598.52
	Caspian	400' west	Ave B	400	12	patch level and resurface; may consider west end of Caspian also but west end not captured here	\$ 8,603.97
	Indian	west end	1st Ave	3,350	12	patch level resurface 1.5"	\$ 81,833.32
	Old Gainseville Road	Lower Bay	Idlewood Dr.	2,040	12	reclamation & pave 2"	\$ 48,939.75
	Idlewood Dr	Old Gainseville	Hwy 90	600	20	Patch; surface 2"	\$ 21,333.33
							\$ 686,874.94 WARD 4 TOTAL
						Engineering	\$ 82,424.99
						Total proje	\$ 769,299.93